


## FLOWMARK DAF TEST

A test was conducted to see what affect FlowMark Electronic DAF Water Treatment would have assisting blood removal from wastewater. Influent to the DAF was pumped from a batch equalization tank that was continuously mixing. Chemical dose and DAF flow rate remained constant during the test. The FlowMark system was energized at 8:56 AM and three FlowMark treated effluent samples were pulled for comparison to the control sample over the following 28 minutes. Turbidity was reduced from 159 NTU to 43 NTU which represents a 72% improvement.



8:55 AM	9:08 AM	9:16 AM	9:24 AM
FlowMark OFF	FlowMark ON	FlowMark ON	FlowMark ON
Turbidity = 159 NTU	Turbidity = 73 NTU	Turbidity = 62 NTU	Turbidity = 43 NTU
Control	Improvement = 54%	Improvement = 61%	Improvement = 72%